

TNO report

www.tno.nl

2005-CVB-R0408

T +31 15 276 30 00
F +31 15 276 30 25

**Fire resistance according to NEN-EN 1364-1:2001
in compliance with NEN 6069:2001 of a Fermacell
wall construction, type 1S21**

Date November 2005
Author(s) Ing. M.N. Slappendel
Dr. Ir. G. van den Berg

Number of pages 15
Number of appendices 4

Contractor Xella Droogbouw Systemen BV
P.O. Box 398
6600 AJ WIJCHEN
The Netherlands

Project name Fire Resistance
Project number 006.55725/01.01

All rights reserved.

No part of this publication may be reproduced and/or published by print, photoprint, microfilm or any other means without the previous written consent of TNO.

In case this report was drafted on instructions, the rights and obligations of contracting parties are subject to either the Standard Conditions for Research Instructions given to TNO, or the relevant agreement concluded between the contracting parties. Submitting the report for inspection to parties who have a direct interest is permitted.

© 2005 TNO

Contents

1	Subject.....	3
2	Examination.....	3
3	Contractor and sponsors.....	3
4	Location and date of test.....	3
4.1	Location.....	3
4.2	Date.....	3
5	Date and number of the report.....	3
6	Test specimen.....	4
6.1	General.....	4
6.2	Wall construction.....	4
6.3	Test frame and supporting construction.....	5
7	Sampling and manufacturing of the construction.....	5
8	Test specimen inspection.....	5
8.1	General.....	5
8.2	Conditioning.....	5
8.3	Determination of density and moisture content.....	5
8.4	Fire test.....	6
9	Observations during the heating.....	6
10	Measurements.....	7
10.1	Measurements.....	7
10.2	Uncertainty of measurement.....	7
11	Summary.....	7
12	Conclusion.....	8
13	Field of application and conditions.....	8
14	Extended application.....	8
14.1	Type of joints.....	8
14.2	Mullions.....	9
14.3	Wall construction 1S24.....	9
Figures	10
Appendices		
A Observations		
B Furnace conditions		
C Position of thermocouples and measurement results		
D Photo's		

1 Subject

Fermacell wall construction, type 1S21, on both sides plated with fermacell gypsum fiber board.

2 Examination

Determination of the fire resistance according to NEN-EN 1364-1:2001 in compliance with NEN 6069:2001.

3 Contractor and sponsors

Xella Droogbouw Systemen BV	Rockwool Benelux BV	Dingemans Elementenbouw BV
P.O. Box 398	P.O. Box 1160	P.O. Box 65
6600 AJ WIJCHEN	6040 KD ROERMOND	5170 AB KAATSHEUVEL
The Netherlands	The Netherlands	The Netherlands

4 Location and date of test

4.1 Location

The investigation took place in the laboratory of the Centre for Fire Research of TNO Built Environment and Geosciences at Rijswijk, the Netherlands.

4.2 Date

The wall construction was assembled on 15 June 2005.
The fire test was executed on 21 June 2005.

5 Date and number of the report

November 2005, 2005-CVB-R0408.

6 Test specimen

6.1 General

A non-load bearing Fermacell wall construction, type 1S21, was investigated. It was assembled from steel studs, filled with mineral wool and finished with fermacell gypsum fiber boards. The fixed edge, bottom and head rail were mounted on the concrete test frame.

6.2 Wall construction

6.2.1 *Steel framework*

The framework was assembled from steel profiles and existed of:

- a Dingemans U-stud 75-06 (5)¹, as bottom and ceiling rail, dimensions 78 x 45 x 0,6 mm;
- a Dingemans C-stud 75-06 (4), as mullions, dimensions 75 x 50 x 0,6 mm. The c.t.c. distance of the mullions was 600 mm.

The U-studs and C-stud on the fixed edge were fixed with plugs and screws (Ø 4 x 50 mm) in the test frame. The c.t.c. distance was 800 mm. Between the test frame and the studs were strips of mineral wool with a thickness of 10 mm.

The U-studs and C-studs were held together by the gypsum fiber boards. The length of the C-stud mullions was 15 mm shorter than the height of the wall, in order to create expanding possibilities.

In order to simulate the width of the wall in practice, the right-hand side (seen from the cold side) was not attached to the supporting construction. In order to give the free-edge the possibility of deflecting there was a strip of Rockwool (thickness 50 mm) placed between the test-frame and the wall construction.

6.2.2 *Filling and finishing*

Between the C-studs plates of mineral wool (Rockwool 204 (Dutch type number), dimensions 1200 x 600 x 70 mm) were clamped.

Fermacell gypsum fiber boards (dimensions 1200 x 2500 x 12,5 mm) were screwed onto the C-studs using fermacell gypsum screws Ø 3,9 x 30 mm. The c.t.c. distance was 250 mm.

On the free-edge a whole board was used, while on the fixed edge an edge panel was used. On the cold side a horizontal board (height 500 mm) was placed on the upper side, on the fire side the horizontal plate was placed on the lower side.

The vertical and horizontal joints were covered with a synthetic wire mesh and then filled with mortar.

¹ The numbers between the parentheses refer to the numbers in figure 3.

6.3 Test frame and supporting construction

Test frame

Material: steel. The lining of the test frame is made of heat resistant concrete. The inner dimensions of the test frame were: 3000 mm x 4000 mm (h x w).

For detailed information concerning the tested construction is referred to the material list and figures 1 - 3 and the photo's in appendix D.

7 Sampling and manufacturing of the construction

Centre for Fire Research TNO
Xella Droogbouw Systemen

- Test frame
- Delivery of materials
- Mounting and assembling of wall construction

8 Test specimen inspection

8.1 General

The materials and components used were inspected during assembly on the basis of the supplied drawings and data.

8.2 Conditioning

During the period of assembly of the construction until the performance of the fire test, the wall was located in the test laboratory at the Centre for Fire Research with an ambient temperature of 20 ± 5 °C and a relative humidity of 50 ± 10 %.

8.3 Determination of density and moisture content

The results of the density²⁾ and the moisture content³⁾ were:

Material	Density [kg/m ³]	Moisture content [%]
Fermacell gypsum fiber board	1140	0,6
Mineral wool	32,6	0,5

²⁾ Determined before drying.

³⁾ Determined by drying during 24 hours at 105 °C, weighing before and after drying. The drying of the Fermacell gypsum fiber board took place at 60 °C.

8.4 Fire test

8.4.1 Conditions

The fire test was carried out according to NEN-EN 1364-1:2001 in compliance with NEN 6069:2001.

The wall construction was heated at one side using the standard fire curve (see figure B.1 in appendix B).

The targeted overpressure in the furnace was 0 Pa at 0.5 m (20 Pa at 3.0 m) above floor level, see figure B.3.

8.4.2 Measurements

During the heating the following measurements were made:

Furnace conditions:

- The gas temperatures in the furnace using 8 plate thermocouples, evenly spread over the directly heated wall surface;
- The pressure in the furnace.

Specimen:

- The surface temperatures on the unexposed side of the wall using 5 thermocouples;
- The surface temperatures on the unexposed side of the wall next to the edges and joints using 16 thermocouples ;
- The heat radiation at a distance of 1.0 m from the geometric centre of the wall structure;
- The horizontal displacement of the wall, in the middle and on the free-edge, measured half way up the wall.

Environment:

- The air temperature in the laboratory outside the furnace.

The positions of the thermocouples on the wall are specified in appendix C.

9 Observations during the heating

After a heating time of 77 minutes a temperature rise of more than 180°C was measured, next to a vertical joint in the wall, *End of thermal insulation with regard to temperature.*

After a heating time of 96 minutes the cotton wool of the cotton pad ignited. The cotton pad was held in front of a joint, *End of integrity with regard to the sealing.*

For a detailed description concerning the observations, is referred to appendix A. The photos in appendix D show the wall before and during the test.

10 Measurements

10.1 Measurements

The measurements are presented in appendix B and C.

10.2 Uncertainty of measurement

Due to the nature of fire resistance testing, in which several non-linear effects are present in both the test configuration and the test specimen, which influence each other, it is at this moment not yet possible to give stated degree of uncertainty of measurement.

11 Summary

The fire resistance of a Fermacell wall construction, type 1S21, is determined. The construction is assembled from:

- steel studs with a filling of mineral wool and finished with gypsum fiber boards.

The fire test was carried out conform NEN-EN 1364-1:2001 in compliance with NEN 6069:2001. The results are summarized in Table 1.

Table 1: Summarized results

Criterion	Time measured from the start of the test during which, conform NEN 6069:2001 and NEN-EN 1364-1:2001, the criterion was reached.		
	NEN 6069:2001	NEN-EN1364-1:2001	Criterion reached or not reached
a) Integrity <ul style="list-style-type: none"> – Cotton wool pad – Opening gauges – Sustained flaming (> 10 sec) 	96 minutes >99 minutes >99 minutes	96 minutes 99 minutes 99 minutes	reached not reached not reached
b) Thermal insulation <ul style="list-style-type: none"> – Average temperature increase – Maximum temperature increase – Radiation 	94 minutes 77 minutes >99 minutes	94 minutes 77 minutes 99 minutes	reached reached not reached

After consulting the contractor the heating was terminated after 99 minutes.

12 Conclusion

The classification in relation to NEN-EN 1364-1:2001 can be given in a separate document conform NEN-EN 13501-2:2004.

Conclusion according to NEN 6069:2001

Because the test, conform NEN-EN 1364-1:2001, is most likely more severe than a test conform NEN 6069:2001, the result is also applicable for the last mentioned.

Fire resistance, concerning the separation function, according to NEN 6069:2001 of the investigated wall construction: **77 minutes**.

13 Field of application and conditions

The conclusion formulated in chapter 12 is only valid for wall constructions, which are the same in detail to the investigated construction, including materials and means of assembly used. Also the following conditions have to be met:

- a) The wall is isolated with mineral with a thickness of at least 70 mm, a density of at least 30 kg/m³ and a melting point greater than 1000 °C.
- b) Mounted in a supporting construction with a minimum density of 2000 kg/m³ and a floor of non-combustible material.
- c) the single span may be increased up to 4 m, only when the following is met:
 - expansion possibilities of the mullions are increased pro rata.
 - horizontal and vertical joints cross at a T-junction.
- d) the width of the wall construction has no limitations.

14 Extended application

In extend to the field of application formulated in chapter 13 the following changes in the construction will, in the opinion of TNO, give a fire resistance of at least **60 minutes**.

14.1 Type of joints

The test was carried out using the Fermacell Tapered Edge joint (3)⁴. Based on test report “P-3854/1372-MPA BS”, d.d. 2 May 2003 from “Materialprüfstalt für das Bauwesen” in Braunschweig, Germany, the following joints, to finish the joint between the vertical and horizontal gypsum fiber boards, are also applicable:

- Fermacell joint filler 5-7 mm joint (2);
- Fermacell butt joint (4);
- Fermacell jointstick, glue filled joint <1 mm (1).

The different types of joints are represented in Figure 4.

⁴ The numbers between the parentheses refer to the numbers in figure 4.

14.2 Mullions

The construction was tested with a c.t.c. distance of the mullions of 600 mm. Taking the surplus value of 17 minutes into account this c.t.c. distance may be increased to 625 mm.

14.3 Wall construction 1S24

Fermacell also delivers a wall construction similar to the one described in this report. This wall construction consists of double mullions as shown in figure 5 and 6. The fire resistance of this wall construction will be at least 60 minutes on condition that the mineral wool between mullions is one of the following combinations:

- 0 mm on one side and 70 mm (density 30 kg/m³) on the other side or,
- 60 mm (density 30 kg/m³) on both sides.



Ing. M.N. Slappendel



Dr.Ir. G. van den Berg

Figures




Figure 1: Overview test specimen, seen from cold side.




Figure 2: Overview test specimen, seen from fire side.




Figure 3: Cross-section overview of test-specimen

Design of vertical FERMACELL joints (steel subframe)

caption:

- 1 FERMACELL Jointstick
• joint: $\leq 1\text{ mm}$
- 2 gap filled with FERMACELL Joint Filler
• width of gap: 5-7 mm
- 3 FERMACELL Tapered Edge
• joint $\leq 1\text{ mm}$
- 4 FERMACELL butt joint
• joint: $\leq 1\text{ mm}$




Figure 4: Overview of the different types of joints.




Figure 5: Cross-section overview of the 1S24 wall construction with 1 layer of mineral wool.




Figure 6: Cross-section overview of the 1S24 wall construction with 2 layers of mineral wool.